

TGUP Campaign Details

Kangulumira Community School Combined Projects Luwero District, Uganda



OVERVIEW:

This document describes the need, elements, and costs of building a new school for the Kangulumira community in Luwero, Uganda. The project includes five subprojects: two classrooms, latrines, a borehole for water, classroom furniture, and an access road to the new school. The total cost is \$33,014.

The current Kangulumira Community School, as seen above, has deteriorated to the point that it can no longer be used.

SUMMARY OF SUB-PROJECTS:

1. **Two new classrooms**: One 52'x21' building will hold two classrooms, each measuring 21'x26'. The building will also have a covered 4' verandah. The classrooms will be built according to local standards, using clay bricks, iron sheet roofing and cement plastering. They will accommodate at least 50 pupils per classroom. The cost for two classrooms: \$19,920

- 2. <u>Latrines</u>: The project will build a latrine block with 4 stalls: 2 for the girls and 2 for the boys. The teachers will also share the latrines with the students. Outside of school hours, the latrines will be open to the estimated 500 community members, most of whom have no access to any other latrines. The dimension of the building will be $10' \times 8'$ and the pit will be 50' deep. Cost: \$3,585
- 3. Borehole for water: A 120' deep borehole will be drilled and installed at the Kangulumira new school site. The borehole will serve the 150 students and the neighboring community of approximately 500 people. The school currently does not have any source for water and the children walk to a borehole approximately 2km away from their current school location to collect water before they begin classes in the morning. Cost: \$4,219



- 4. <u>Classroom furniture</u>: The project will provide 30 classroom benches with attached desks. The desks and benches will have a metal frame and wood surfaces. Each desk and bench will seat 5 students so this project will accommodate 150 students. Currently, the students sit on the floor and write using tree stumps instead of desks. Cost: \$4,625
- 5. <u>Access road</u>: An access road will be cleared, compacted, and murram (rock) will be laid for easy access to the new school site. The access road will be approximately 300 feet long connecting to the main road. Cost: \$665

BUDGET SUMMARY:

| Classrooms: | | \$ | 19,920 |
|-------------|-------|-----|--------|
| Latrines | | \$ | 3,585 |
| Borehole | | \$ | 4,219 |
| Furniture | | \$ | 4,625 |
| Access road | | \$ | 665 |
| | Total | \$: | 33 014 |

Total: \$33,014

PROJECT PARTNERS:

The Global Uplift Project (TGUP) helps American donors build small-scale educational infrastructure projects in developing countries from donations as small as one dollar. Since its founding in 2007, TGUP has completed more than 400 such projects in 26 countries in Asia, Central America, and Africa. Over their expected duration, those projects will help more than 2.3 million of the poorest people in the world have just a slightly better chance in life. TGUP is a registered 501c3 nonprofit.

Nsawo Community Development Project (NCDP) started in 2023 with backing from Rotary International clubs and TGUP. The founding project was a *Save a Girl* ™ Sewing Center. NCDP is a registered nonprofit community-based organization in Kampala, Uganda. Since registering as a nonprofit, it has completed many small projects for TGUP.

PROJECT MANAGEMENT:

The Global Uplift Project

Sponsoring Executive: Supervising Executive:

Robert Freeman Cathy Dwulet

Executive Director Director, Global Field Operations

robertf@tgup.org cathyd@tgup.org 650-575-3434 650-269-5598

Nsawo Community Development Project

Senior Executive: Supervising Executive:

Deb Kulubya Herbert Muyinga Founder, NCDP Director, NCDP


kimydala@yahoo.co.uk hmuyinga@yahoo.com +256 752 666998 +256 772 720 558

PROJECT DATES: As soon as funding is completed. Three to four months

from start to finish. Likely start date: March 2024.

THE COMMUNITY:

Kangulumira village is a typical rural community located in the central region of Uganda. Most families earn less than 2 dollars per day and live below the UN poverty line. Illiteracy and birth rates in the community are quite high, with girls being most vulnerable.





guerilla war between 1981- 1986. It has a growing population of over 20,000 inhabitants, 90% of whom are poor peasant farmers who carry out subsistence farming for their livelihood.

THE SCHOOL:

The Kangulumira Parents' Primary School is a community school that was built two years ago by hand out of papyrus reeds by the local people. The school has 4 rudimentary classrooms and is attended by very poor village children aged 4-12 years. The establishment of the school facilitated attendance for children who had no access before and/or who used to walk long distances (5+ miles each way, every day) to attend other schools.

A total of 150 pupils currently attend the school, of which 82 are girls and 68 are boys. The school is managed by the Peasant Community Teachers and Parents Association who often struggle to raise funds to pay the 4 teachers employed to teach in the school. The pupils are supposed to pay 80,000 Ugandan shillings per term (about \$20). Many pay in small amounts as the harvests come in, and some don't pay at all. But the community and teachers are committed to this school, even going without pay if needed.

The school enrollment has gone beyond the available number of classrooms and the reed walls of the classrooms are falling apart. The 3rd and 4th grades share one classroom with pupils facing opposite directions during lessons.



The current enrollment of 150 pupils is as follows:

Nursery 1 = 42 Nursery 2 = 20 Class 1 = 32 Class 2 = 20 Class 3 = 18

Class 4 = 18

DETAILED BUDGETS:

| Two classrooms | | | | | | |
|----------------|----------|---------|---------------------------|--------------------------|--|--|
| Item | Quantity | Rate | Uganda Shillings (USH) | US Dollars (\$) @3900 | | |
| FOUNDATION | | | | | | |
| Bricks | 10,800 | 500 | 5,400,000 | \$1,384.62 | | |
| Lake sand | 4 Trips | 300,000 | 1,200,000 | \$307.69 | | |
| Plaster sand | 2 Trips | 250,000 | 500,000 | \$128.21 | | |
| Cement | 65 Bags | 35,000 | 2,275,000 | \$583.33 | | |
| Poles | 32 Pcs | 5,000 | 160,000 | \$41.03 | | |
| Wood Timbers | 42 Pcs | 8,000 | 336,000 | \$86.15 | | |
| YIZ Steel bar | 8 Pcs | 45,000 | 360,000 | \$92.31 | | |
| R.7 Ringwires | 6 Pcs | 10,000 | 60,000 | \$15.38 | | |
| Binding wires | 6 Kgs | 6,000 | 36,000 | \$9.23 | | |
| Nails | 8 Kgs | 6,000 | 48,000 | \$12.31 | | |
| Aggregate | 7 Trips | 300,000 | 2,100,000 | \$538.46 | | |
| Hard core | 6 Trips | 250,000 | 1,500,000 | \$384.62 | | |
| B.R.C Mesh | 4 Rolls | 300,000 | 1,200,000 | \$307.69 | | |
| Paper Sheet | 2 Rolls | 300,000 | 600,000 | \$153.85 | | |
| Marrum soil | 11 Trips | 120,000 | 1,320,000 | \$338.46 | | |
| Transport | | | 300,000 | \$76.92 | | |
| | | Labour | 3,000,000 | \$769.23 | | |
| WALLS | | | | | | |
| Bricks | 18000 | 500 | 9,000,000 | \$2,307.69 | | |
| Lake sand | 4 Trips | 300,000 | 1,200,000 | \$307.69 | | |
| Plaster sand | 2 Trips | 250,000 | 500,000 | \$128.21 | | |

| Cement | 60 Bags | 35,000 | 2,100,000 | \$538.46 |
|--------------------------------|----------|-----------------|--------------|-------------|
| Poles | 32 Pcs | 5,000 | 160,000 | \$41.03 |
| Wood Timbers | 42 Pcs | 8,000 | 336,000 | \$86.15 |
| YIZ Steel bar | 35 Pcs | 45,000 | 1,575,000 | \$403.85 |
| R.7 Ringwires | 25 Pcs | 10,000 | 250,000 | \$64.10 |
| Binding wires | 11 Kgs | 6,000 | 66,000 | \$16.92 |
| Nails | 13 Kgs | 6,000 | 78,000 | \$20.00 |
| Aggregate | 2 Trips | 300,000 | 600,000 | \$153.85 |
| Painting | | | 5,653,000 | \$1,377.01 |
| Transport | | | 300,000 | \$76.92 |
| | | Labour | 2,600,000 | \$666.67 |
| PLASTERING | | | | |
| Plaster sand | 6 Trips | 250,000 | 1,500,000 | \$384.62 |
| Lake sand | 2 Trips | 300,000 | 600,000 | \$153.85 |
| Cement | 116 Bags | 35,000 | 4,060,000 | \$1,041.03 |
| Slate stone | 2 Trips | 450,000 | 900,000 | \$230.77 |
| Windows | 10 Pcs | 500,000 | 5,000,000 | \$1,282.05 |
| Doors | 2 Pcs | 1,000,000 | 2,000,000 | \$512.82 |
| Transport | | | 300,000 | \$76.92 |
| - | | Labour | 1,800,000 | \$461.54 |
| ROOFING | | | | |
| 6 x 2 Timbers | 36 Pcs | 12,000 | 432,000 | \$110.77 |
| 4 x 3 Timbers | 17 Pcs | 12,000 | 204,000 | \$52.31 |
| 4 x 2 Timbers | 127 Pcs | 8,000 | 1,016,000 | \$260.51 |
| 3 x 2 Timbers Hook | 127 Pcs | 6,500 | 825,500 | \$211.67 |
| Iron | | | | |
| Hook Iron | 2 Rolls | 40,000 | 80,000 | \$20.51 |
| Iron Sheets | 80 Pcs | 55,000 | 4,400,000 | \$1,128.21 |
| Ridges | 11 Pcs | 20,000 | 220,000 | \$56.41 |
| Nails 6" | 21 Kgs | 6,000 | 126,000 | \$32.31 |
| 5" | 21 Kgs | 6,000 | 126,000 | \$32.31 |
| 4" | 21 Kgs | 6,000 | 126,000 | \$32.31 |
| 3" | 15 Kgs | 6,000 | 90,000 | \$23.08 |
| Roofing Nails | 21 Kgs | 7,000 | 147,000 | \$37.69 |
| Fasier Boards | 20 Pcs | 25,000 | 500,000 | \$128.21 |
| Transport | | | 300,000 | \$76.92 |
| Permits & Inspection | | | 850,000 | \$217.95 |
| | | Labour | 2,200,000 | \$564.10 |
| Community Contribution | | (6,696,250) | (\$1,716.99) | |
| Project management & reporting | | | 12,053,250 | \$3,090.58 |
| | • | Total requested | 77,972,500 | \$19,920.47 |

| Latrines | | | | | |
|--------------------------------|-----------|------------|------------------------------|--------------------------|--|
| Item | Quantity | Rate | Uganda Shillings (USH) | US Dollars (\$) @3900 | |
| Bricks | 3,500 | 500 | 1,750,000 | \$448.72 | |
| Plaster sand | 1 Truck | 400,000 | 400,000 | \$102.56 | |
| Lake sand | 1 Truck | 400,000 | 400,000 | \$102.56 | |
| Aggregate stones | 1 Truck | 250,000 | 250,000 | \$64.10 | |
| Cement | 50bags | 35,000 | 1,750,000 | \$448.72 | |
| Steel bars Y12 | 3 Pieces | 50,000 | 150,000 | \$38.46 | |
| Steel bars Y16 | 3 Pieces | 80,000 | 240,000 | \$61.54 | |
| 4*2 Timber | 22 Pieces | 7,000 | 154,000 | \$39.49 | |
| Wood Timber | 30 Pieces | 10,000 | 300,000 | \$76.92 | |
| Nails | 6 Kgs | 6,000 | 36,000 | \$9.23 | |
| Payan | 2 Rolls | 10,000 | 20,000 | \$5.13 | |
| Pipe | 2 | 12,500 | 25,000 | \$6.41 | |
| Wire Mesh | 4 Pieces | 30,000 | 120,000 | \$30.77 | |
| Doors | 4 Pieces | 300,000 | 1,200,000 | \$307.69 | |
| Iron sheets | 8 Piece | 55,000 | 440,000 | \$112.82 | |
| Excavation | 50ft | 30,000 | 1,500,000 | \$384.62 | |
| Poles | 15 Pieces | 10,000 | 150,000 | \$38.46 | |
| Facier Boards | 6 Pieces | 35,000 | 210,000 | \$53.85 | |
| Labor | | | 1,800,000 | \$461.54 | |
| Transportation | | | 100,000 | \$25.64 | |
| Painting | | | 1,100,000 | \$282.05 | |
| Permits & Inspection | | | 850,000 | \$217.95 | |
| Community contribution | | | (1,294,500) | (\$331.92) | |
| Project management & reporting | | | 2,330,100 | \$597.46 | |
| | requested | 13,980,600 | \$3,584.77 | | |

| Borehole | | | | | | |
|-----------------|--------------|---------|------------------------------|--------------------------|--|--|
| Item | Quantit y | Rate | Uganda Shillings (USH) | US Dollars (\$) @3900 | | |
| Drilling | 120ft | 50,000 | 6,000,000 | \$1,538.46 | | |
| Bricks | 6,000 | 500 | 3,000,000 | \$769.23 | | |
| Lake sand | 1 Trip | 230,000 | 230,000 | \$58.97 | | |
| Ordinary Cement | 25bags | 35,000 | 875,000 | \$224.36 | | |
| Pedestal | 1 | 780,000 | 780,000 | \$200.00 | | |

| Water stand | 1 | 350,000 | 350,000 | \$89.74 |
|--------------------------------|--------|---------|-------------|------------|
| Binding Wire | 1kg | 20,000 | 20,000 | \$5.13 |
| Steel Rods | 1 Pc | 170,000 | 170,000 | \$43.59 |
| Aggregate Stones | 1 Trip | 220,000 | 220,000 | \$56.41 |
| Poles | 6 Pcs | 10,000 | 60,000 | \$15.38 |
| Waterproof Cement | 2 Bags | 150,000 | 300,000 | \$76.92 |
| Nails | 2Kg | 15,000 | 30,000 | \$7.69 |
| Pipes | 15 Pcs | 80,000 | 1,200,000 | \$307.69 |
| Borehole Head | 1 Pc | 550,000 | 550,000 | \$141.03 |
| Connecting Rods | 10 | 85,000 | 850,000 | \$217.95 |
| Cylinder Head | 1 Pc | 600,000 | 600,000 | \$153.85 |
| Community Contribution | | | (1,523,500) | (\$390.64) |
| Project management & reporting | | | 2,742,300 | \$703.15 |
| Total requested | | | 16,453,800 | \$4,218.92 |

| Classroom Furniture (bench/desks) | | | | | |
|--|---------------|-----------|------------------------------|--------------------------|--|
| Item | Quantity | Rate | Uganda Shillings (USH) | US Dollars (\$) @3900 | |
| Desks attached to benches (Metallic frame) | 30 (5 seater) | 550,000 | 16,500,000 | \$4,230.77 | |
| Transportation | | | 200,000 | \$51.28 | |
| Community contribution | | | (1,670,000) | (\$428.21) | |
| Project management & reporting | | | 3,006,000 | \$770.77 | |
| | Total r | requested | 18,036,00 0 | \$4,624.62 | |

| Access Road | | | | | |
|----------------------------------|---------------|-----------|------------------------------|--------------------------|--|
| Item | Quantity Rate | | Uganda Shillings (USH) | US Dollars (\$) @3900 | |
| Bush clearing & uprooting stumps | | | 1,800,000 | \$461.54 | |
| Murrum & compacting | | | 600,000 | \$153.85 | |
| Community contribution | | (240,000) | (\$61.54) | | |
| Project management & reporting | | 432,000 | \$110.77 | | |
| Total requested | | 2,592,000 | \$664.62 | | |